

## Verifying the Status of a LAG Interface

---

**Purpose** Verify that a LAG (ae0) has been created on the switch.

**Action** show interfaces ae0 terse

Interface	Admin	Link	Proto	Local	Remote
ae0	up	up			
ae0.0	up	up	inet	10.10.10.2/24	

**Meaning** The output confirms that the ae0 link is up and shows the family and IP address assigned to this link.

**Related Topics**

- Configuring Aggregated Ethernet Interfaces (CLI Procedure)
- Configuring Link Aggregation (J-Web Procedure)
- Example: Configuring Aggregated Ethernet High-Speed Uplinks Between a Virtual Chassis Access Switch and a Virtual Chassis Distribution Switch

