

Verifying the Status of a LAG Interface

Purpose Verify that a LAG (ae0) has been created on the switch.

Action show interfaces ae0 terse

Interface	Admin	Link	Proto	Local	Remote
ae0	up	up			
ae0.0	up	up	inet	10.10.10.2/24	

Meaning The output confirms that the ae0 link is up and shows the family and IP address assigned to this link.

- Related Topics**
- Configuring Aggregated Ethernet Interfaces (CLI Procedure)
 - Configuring Aggregated Ethernet Interfaces (J-Web Procedure)
 - Example: Configuring Aggregated Ethernet High-Speed Uplinks Between a Virtual Chassis Access Switch and a Virtual Chassis Distribution Switch

Published: 2009-07-22